

Site Data

Current Zoning	MXD/PCD Overlay
Proposed Zoning	MXD/PCD Overlay
Current Land Use	MXD
Proposed Land Use	MXD
Total Site Area	683.98 Ac.
Density	
RH - up to 15 DU/A.C.	
RM - up to 9 DU/A.C.	
RL - up to 5 DU/A.C.	
Section/Township/Range	26,35/41/142

Development Program

West Parcel	206.00 Ac.
Single Family	485 units
East Parcel	475.69 Ac.
Medical Office	160,000 sq.ft.
Office	1,200,000 sq.ft.
Hospital	450 Beds
Retail	450,000 sq.ft.
Apartments	353 units
Multifamily	681 units
Single Family	533 units
Assisted Living Facility	256 beds
Industrial/ R&D/ Biotech	1,600,000 sq. ft.

Site Area Breakdown


Parcels	555.97 Ac.
Parcel A - Scripps Campus District	69.86 Ac.
Parcel B - Biotech District	99.91 Ac.
Parcel C - Town Center District	133.68 Ac.
Parcel D - Neighborhood District	27.76 Ac.
Parcel E - Neighborhood District	43.88 Ac.
Parcel F - Neighborhood District	31.30 Ac.
Parcel G - Neighborhood District	144.58 Ac.
Utility	5.00 Ac.
Upland Preserve Area	
Required	95.33 Ac.
Provided (includes .71 Ac. Archaeologically Significant Site)	83.26 Ac.
Onsite	83.26 Ac.
Offsite	12.34 Ac.
Total	95.6 Ac.
Wetland Area (including buffers)	8.36 Ac.
*Lakes including LME (included in parcels)	92.36 Ac.
PCD Buffers (included in parcels)	10.63 Ac.**
ROW Buffers (included in parcels)	12.40 Ac.
Utility Easement (Adjacent to Hood Road Preserves)	0.59 Ac.
Right of Ways	28.62 Ac.
Rec. Area	3.50 Ac.
Entry Feature Open Space	1.39 Ac.
Total	681.69 Ac.

Open Space Calculations

Total Site Area	681.69 Ac.
Required Open Space (20% Min. Required)	136.34 Ac.
Provided Open Space	163.73 Ac. (24%)
Preserve Area	68.17 Ac.
Upland Preserve	60.67 Ac.
Wetland Area	7.50 Ac.
Wetland/ Preserve Buffers	0.86 Ac.
PCD Buffers	11.38 Ac.**
ROW Buffers	12.40 Ac.
Lakes (including LME)	68.17 Ac.
Rec. Parcel	1.75 Ac.

** Open Space Tracts O-1 through O-4 are included in the PCD Buffers

Location Map



Urban design studio
 Urban Planning & Design
 Landscape Architecture
 Communication Graphics

610 Clematis Street, Suite CU02
 West Palm Beach, FL 33401
 561.366.1100 FAX 561.366.1111
 www.udsf.com
 MLCC000035

MXD Land Allocation

Open Space	
Required*	20%
Proposed**	20%
Commercial	
Maximum	30%
Proposed	8%
Employment Center	
Minimum	20%
Maximum	60%
Proposed	25%
Residential Low	
Minimum	2%
Maximum	35%
Proposed	35%
Residential High	
Minimum	5%
Maximum	35%
Proposed	12%

MXD Lot Coverage


Commercial	
Maximum	50%
Proposed	50% Max
Employment Center	
Maximum	70%
Proposed	70% Max
Residential	
Maximum	50%
Proposed	50% Max

MXD Height

Commercial	
Maximum	4 Floors
Proposed	4 Floors
Employment Center	
Maximum	150 Feet
Proposed	150 Feet
Residential	
Maximum	4 Floors
Proposed	4 Floors

Above allocations are based on the gross acreage of the project.
 *Pursuant to pending Comprehensive Plan Amendment.
 **See Development Order Conditions of Approval.

Legend



Conversion of Uses

- 4 East Parcel Multi-Family units to 3 East Parcel Apartments
- 600 West Parcel Multi-Family units to 222 West Parcel Single Family units
- 35 West Parcel Apartments to 13 West Parcel Single Family units
- 314 West Parcel Apartments to 116 East Parcel Single Family units
- 35,000 s.f. of West Parcel Commercial area to 67 East Parcel Single Family units
- 1 Apartment to PCD Credit Bank
- 15,000 s.f. of West Parcel Commercial to 32,000 s.f. of East Parcel Research & Development
- 115 East Parcel Multi-Family Uses to 256-bed ALF in East Parcel

* The Residential units approved for Parcels C, D, E and F (1,567 units) and identified on the PCD Master Plan may be relocated at the discretion of the property owner from among Parcels C, D, E, and F as long as the maximum densities below are not exceeded:
 i. Parcel C - RH: 15 du/ac
 ii. Parcel D - RL: 5 du/ac
 iii. Parcel E - RH: 15 du/ac
 iv. Parcel F - RM: 9 du/ac

The relocation of residential units shall require the consent of both sending and receiving property owners and shall require the PCD Master Plan to be updated via Resolution. The updated PCD Master Plan will be on file with the City of Palm Beach Gardens.

Notes

*Lakes shown are conceptual in configuration and are for drainage purposes. Additional lake locations, sizes, and configuration to be determined at the time of Final Site Plan approval for each parcel. See Design Guidelines for additional regulations. See Upland Preserve Mitigation Plan for upland area details. Parcel acreages are not inclusive of Preserve or Wetland.

Copyright:
 All ideas, designs, arrangements, and plans represented by this drawing are owned by and the property of the designer, and were created for the exclusive use of the specified project. These ideas, designs, arrangements or plans shall not be used by, or disclosed to any person, firm, or corporation without the written permission of the designer.

Date: 01.09.09
 Project No.: 88-039.019
 Designed By: SCMLMB
 Drawn By: SCMLMB
 Checked By: KT

Submittal Dates : Comments
 02.02.09 SCM PCD Resubmit
 09.11.09 SCM PCD Resubmittal
 10.08.09 LMB PCD Resubmittal
 11.16.09 LMB PCD Resubmittal
 11.24.09 LMB PCD Resubmittal
 03.02.10 HLC Revisions
 01.11.11 SCM Seacoast
 02.08.13 SCM FPL Revisions
 10.02.13 SCM ROW Revisions
 12.19.13 SCM PCD Resubmittal

01.27.14 SCM PCD Resubmittal
 03.06.15 TLM PCD Resubmittal
 05.08.15 TLM PCD Resubmittal
 07.31.15 TLM PCD Resubmittal
 09.04.15 TLM PCD Resubmittal
 10.23.16 TLM PCD Resubmittal
 07.26.16 JEB PCD Resubmittal
 09.07.16 BB PCD Resubmittal
 09.20.16 BB PCD Resubmittal
 08.29.17 BB Wall Revisions
 08.31.17 BB Resubmittal
 04.10.18 BB REVISIONS
 10.22.18 BB Revisions
 12.23.20 RD PCD Submittal
 06.23.21 RD PCD Resubmittal

Alton PCD
Palm Beach Gardens, Florida
PCD Master Plan

Drawing name: H:\008\Bldg\Trac_JacobKroger_Palms_GA_H_SPP_0180\Design\Master_Plan\MP_001_08.23.09

Sheet 1 of 1

Scale: 1" = 400'-0"

0 200' 400' 800'

NORTH